

ADDENDUM NO. 3

DATE: August 12, 2020

PROJECT:

MERCED COLLEGE HEALTH CENTER PROJECT
MCCD BID NO. 2020-04


OWNER:

MERCED COMMUNITY COLLEGE DISTRICT
3600 M Street
Merced, CA 95348

ARCHITECT:

DARDEN ARCHITECTS, INC.
Attention: Grant E. Dodson
6790 N. West Avenue
Fresno, California 93711
T. (559) 448-8051
F. (559) 446-1765

DARDEN PROJECT NO. 1954
DSA File Nos. 24-C1
DSA APPL. NO. 02-118108



It will be the responsibility of the General Contractor to submit the information contained in this addendum to all its subcontractors and suppliers. Acknowledge receipt of this Addendum in the space provided on the Bid Form. Failure to do so may subject Bidder to disqualification.

The following additions, deletions, and revisions to the SHEETS and Project Manual are hereby made and do become a part of these Contract Documents.

PROJECT: MERCED COLLEGE HEALTH CENTER PROJECT

ADDENDUM NO. 3DATE: August 12, 2020
PAGE 2

INDEX OF ADDENDA TRANSMITTED HEREWITH

PROJECT MANUAL:

BIDDING AND CONTRACT REQUIREMENTS:

CHANGES TO PRIOR ADDENDA AD3-CPA01 THRU AD3-CPA04

PROJECT MANUAL:

BIDDING AND CONTRACT REQUIREMENTS:

CHANGES TO PRIOR ADDENDA:

AD3-CPA01 Refer to Addendum No.2 item AD2-SP03

1. Omit Specification Section 012113, ALLOWANCES from the project manual.

AD3-CPA02 Refer to Addendum No.2 attachment AD2-AX03_A/A301, DEMOLITION ROOF PLAN & ROOF PLAN:

1. Refer to Roof Plan Legend at K18 and add the following note.
 - i. "2. Warrantied roof patch for the 2-inch Conduit feeding the new SF-1, roof penetration installed by the owner. See Electrical."

AD3-CPA03 Refer to Addendum No.2 attachment AD2-EX02_A/E001, OVERALL ELECTRICAL PLAN:

1. Refer to P12, GENERAL ELECTRICAL NOTES and add the following note.
 - i. "10. The health center category data cables should be provided and routed to the new IDF. The owner's low voltage contractor will be responsible terminating the cables into the new IDF."
2. Refer to DRAWING KEY NOTES and add the following statement to keynote 2.
 - i. "The 112.5 KVA transformer provided and installed by owner."
3. Refer to DRAWING KEY NOTES and add the following statement to keynote 3.
 - i. "The new panel 'PL' provided and installed by owner."
4. Refer to DRAWING KEY NOTES and replace keynote 5 with the following statement.
 - i. "5. New 2"C-3#2/0, 1#6 GND. provided and installed by owner."
5. Refer to DRAWING KEY NOTES and replace keynote 6 with the following statement.
 - i. "6. New 4"C-4#500KCMIL, 1#1/0 GND. provided and installed by owner."
6. Refer to DRAWING KEY NOTES and replace keynote 7 with the following statement.
 - i. "7. New 2"C-4#3/0, 1#6 GND. provided and installed by owner."

PROJECT: MERCED COLLEGE HEALTH CENTER PROJECT

ADDENDUM NO. 3**DATE: August 12, 2020**
PAGE 4

7. Refer to DRAWING KEY NOTES and replace keynote 11 with the following statement.
 - i. *"11. Delete the work required to remove the existing Data IDF Rack and to re-terminate the existing incoming fiber optic cable and the existing 354 Category data outlet cables, from the existing IDF Rack, to the new IDF Data Racks under Key Note 11; This work will be performed by the Owner's Low Voltage Contractor under a separate contract."*

8. Refer to DRAWING KEY NOTES and replace keynote 13 with the following statement.
 - i. *"13. Delete providing the new two post data racks under Keynote 13; This work will be performed by the Owner's Low Voltage Contractor under a separate contract."*

9. Refer to DRAWING KEY NOTES and replace keynote 14 with the following statement.
 - i. *"14. Delete the new cable runners under Keynote 14. This work will be performed by the Owner's Low Voltage Contractor under a separate contract."*

AD3-CPA04 Refer to Addendum No.2 attachment AD2-EX04_A/E201, ELECTRICAL PLAN:

1. Refer to DRAWING KEY NOTES and add the following statement to keynote 2.
 - i. *"Owner to remove existing panel 'SF1' (Load Center) and verify existing circuits to remain and connect to new panel 'SF1'."*

2. Refer to DRAWING KEY NOTES and replace keynote 5 with the following statement.
 - i. *"5. New panel 'SF1' provided and installed by owner."*

END OF ADDENDUM NO 3.